ADDENDUM NO. 2

Bid Date: May 29, 2024 4:00 p.m. CDT

TO ALL BIDDERS: Renovations of the Library on the Kemper Campus Boonslick Regional Library – Cooper County Branch

THIS ADDENDUM SHALL SUPERSEDE THE PLANS AND SPECIFICATIONS INSOFAR AS IT IS IN DISAGREEMENT WITH THE SAME. HOWEVER, IT WILL IN NO WAY RELIEVE THE CONTRACTOR OF ANY RESPONSIBILITY UNDER THE PLANS AND SPECIFICATIONS, EXCEPT AS HEREIN SPECIFICALLY STATED.

All Addenda's will be provided via e-mail to all Plan Rooms and any General Contractors on the Plan Holders List. All other Contractors and Vendors to obtain a copy of the Addenda's from one of the above.

Architectural Items:

Item No. A01 – CLARIFICATION – Drawings, Demolition Plan sheet A101

- Existing Ceramic Tile located in the following locations: Vestibule and Stair at main level....floors and base. Restrooms main level.....floor and full height on 4 interior walls. Exterior wall at north restroom is brick and is to remain brick. Restrooms lower level.....floor and full height on all 4 interior walls.
- 2) All ceramic tile is to be removed.
- 3) All other existing areas have either carpet or vct and are to be removed.
- 4) See attached sheets for locations.

Item No. A02 – CLARIFICATION – Signage

- 1) Interior ADA Signage See specification Section 101400. This signage is to be in the base bid of this project. See the attached schedule for locations.
- Exterior Cast Metal Letters See specification Section 101419. This signage is to be in the base bid of this project and is to be the custom font as shown. See exterior elevation sheet A301 for details.
- 3) Interior Signage Allowance This is for interior way finding, etc. that has not been established as of yet. The allowance will be used for material and labor for installation.
- 4) Monument Signs The concrete bases for the two monument signs is Alternate #3. The actual signage will be by others.

Item No. A03 – CLARIFICATION – Painting

- 1) The ceilings of the stairway at all levels is to be painted.
- 2) The new wall at Mechanical-018 is to be finished and painted.
- 3) Round Windows Interior and exterior painting to include all items currently painted white, including inset muntins on interior and exterior.
- 4) Where there is ceramic tile on the wall in any location, the remainder of the wall is to be painted.

Item No. A04 – CLARIFICATION – Existing Metal Railings interior and exterior.

 Exterior railings at exterior of the building at the main entrance to the south and the west entrance at the ramp are not scheduled to be painted. The atrium guard rail on the interior is also not scheduled to be painted. These rails are to be protected from damage at all times. Any damage caused during the construction period will be the responsibility of the contractor to repair/replace.

Item No. A05 – CLARIFICATION – Gel Staining of existing stained/varnished oak elements.

1) Field testing on existing trim to be performed to achieve desired color prior to application to all existing elements.

Structural Items: None this Addendum

MEP Items:

Item No. MEP01 - CLARIFICATION - Plumbing above Ceiling

- 1) Plumbing drain, waste, and vent PVC piping installed in the ceiling space of Main Level Family RR 105 and 106 is located in a plenum return.
- At contractor's option, do one of the following for plenum exposed DWV pipe:
 a. Insulate PVC DWV pipe with 1/2" insulation per specifications
 b. Install no-hub cast iron DWV piping.

Item No. MEP02 – CLARIFICATION – Upper Level Power Plan – Sheet E112


- 1) See note one on Sheet E112.
- 2) EXACT location of these new floor devices will be determined by the architect and owner. See plan on the Sheet for locations. These locations may move to the center of each book shelf and should be bid accordingly.


Item No. MEP03 - ADD - Power/Data at entrances


- 1) Add a power and data outlet in wall at the following entrance locations for traffic counters: Door 001, Door 012, Door 113b
- 2) Connect to nearest circuit.

Approved Substitution Requests: None this Addendum

Attachments:	Item A01 – Ceramic Tile Demolition -	2 pages
	Item A02 – ADA Signage -	1 page
	Current GC Plan holder List:	1 page







PLAN HOLDERS LIST - 05-24-2024

PROJECT:

Bids Due:

Renovations of the Library on the Kemper Campus - Boonville, MO

Wednesday, May 29th, 2024 - 4:00 pm, CDT

Bids will be received at the Project Location 707 Third Street - Boonville, MO 65233 Bids will be opened and read aloud at that time.

GENERAL CONTRACTORS

GBH Builders Jake Hunget estimating@gbhbuilders.com

GloveCon Incorporated Jake Long jake.long@glovecon.com

Prost Builders, Inc. Vaughn Prost estimating@prostbuilders.com

Septagon Construction Billy Wundrack bwundrack@septagon.com

Weldon Builders and Construction Howard Weldon Scott Weldon howard@weldonbuilt.com scott@weldonbuilt.com P.O. Box 945, 3441 N. Ten Mile Drive Jefferson City, MO 65109 Phone 573.893.3633

> 1200 South Business 54 Fulton, MO 65251 Phone 573.642.6363

P.O. Box 1727 Jefferson City, MO 65102 Phone 573.635.0211

> 3805 Mohave Court Columbia, MO 65202 Phone 573.442.6187

924 Main Street Trenton, MO 64683 Phone 660-247-3207

ARCHITECT: Porter, Berendzen & Associates, P.C. 573-657-2022 / jay@pba-architecture.com

200 South Henry Clay Blvd. - P.O. Box 446 Ashland, MO 65010

For informational purposes only. This list is subject to change. Additional Contractors / Sub-Contractors / Suppliers not included on this list may Bid the Project. Contractors / Sub-Contractors / Suppliers included here may elect not to Bid the Project.